

JOB STORY

Trenching:

Atlanta Airport
Delta Air Lines TOC Project

Dā-mite®

Excavation, electrical lines, Atlanta Airport, Delta Air Lines TOC Project; prime contractor New South Construction, Forest Park GA. During course of construction, rock was uncovered in the path of the electrical power system. Site had "no blasting" specifications. Four pits that were 14'x14'x14' deep and 500 feet of 6' x 6' deep trench had to be excavated in solid rock. Daigh provided supervision, drilling with subcontractors and expansive material. A continuous slot was cut in the rock with drilling equipment to create a free breaking face.



Drilling Slots.



Continuous slots cut into the rock to create a free break face.



Good cross cracking.



Drill pattern and wall channeling.

