

Daigh Company Job Stories

#18a Gas Compressor Station

Transco Greenville Mississippi Pump Station. Gas Compressor foundation was removed inside active pump station during plant upgrade. Job was drilled with IR ECM air track using 1 5/8" holes. Excavation was done with mini excavators.



View above left of compressor before removal, drilling inside with Track Drill using water for dust control. Middle left looking down on drill and foundation which was 24 x 19 feet. Above, cracking starting and left, cracking on foundation as seen from basement.