

Daigh Company Job Stories

#23a Pre Split for Subway Project Queens NY



2 3/4" holes were drilled with depth up to 24 feet on 1 ft centers 3 ft from existing subway wall. Every other hole was loaded,



Cracking occurred from hole to hole full depth. Dā-mite was loaded in sleeved holes due to wet conditions in the holes.



Note the clean break line that was achieved from the Dā-mite after blasting.