## **JOB STORY**

**Concrete:** 

Reinforced Concrete Dam Demolition in Deleware



Da-mite was used to crack reinforced concrete to aid in demolition of a Dam. Drilled 2" holes with Sandvik 700 Track Drill, Depth: 11-12 feet per lift. Drill Pattern was 18" centers, due to the way rebar was laying in the concrete.

Drilling 2" holes

Loading Da-mite

