

JOB STORY

Concrete:

Gas Compressor
Foundation Removal
Greenville, Mississippi

Dā-mite®

Williams Energy:
Transco Greenville Mississippi
Pump Station.

Gas Compressor foundation
was removed inside active
pump station during plant
upgrade.

Job was drilled with IR ECM
air track using 1 5/8" holes.

Before Removal (top)

Drilling inside with Track Drill
using water for dust control.





View from above:
Drill & Foundation 24' x 19'



• Cracking begins



• Cracking in foundation as
seen from basement.

