JOB STORY

Dā-mite

Mass Rock: Pre-split Subway Project Queens, NY

2^{3/4}" holes were drilled with a depth up to 24 feet on 1ft centers 3ft from existing subway wall.

Pre-split line drill pattern.

Every other hole • was loaded.





Cracking occurred from hole to hole full depth.



Da-mite was loaded in sleeved holes due to wet conditions in the holes.



Note the clean break line that was achieved from Da-Mite after blasting.

