

JOB STORY

Concrete:

Wall Trimming
Warwick, Rhode Island



Da-mite

New bridge construction
Partial demo of wall on
highway bridge for access
for a Caisson Rig.

Gas main was behind wall
and local gas company was
on strike. Sawcut at limits
of break and cut rebar
which included imbedded
3 ft square column rebar.
Trimmed a crescent shaped
piece out of wall and left
1 ft thick section. Loaded
Da-mite Rock Splitting Mortar
in 8 hour delays to keep from
breaking in wrong direction.

Top: Drilling 16 ft. deep with
Tamrock 300 Commando.

Middle: Cracks in wall,
Da-mite pushed concrete
out about 1 inch.

note sawcut





Pulling over with excavator.



Concrete broke along lines of holes.

• Note Da-mite Rock Splitting Mortar in holes.

• Slab on ground.



Daigh Company, Inc. 2393 Canton Hwy, Suite 400, Cumming, GA 30040
P: 770-886-4711 F: 770-887-3783 sales@daighcompany.com www.da-mite.com